Garbett Construction Inc

The Elizabeth Plan | Salt Lake City, UT











PROJECT DATA

- **Layout:** 4 bed, 3.0 bath, 2 fl, 5211 ft^2
- **Climate:** 2021 IECC Cold Dry
- **Category:** Production

Modeled Performance Data

- **ERI:** without PV 50
- **Annual Energy Costs:** without PV $1,680
- **Annual Energy Cost Savings:** without PV $1,200
- **Savings in the First 30 Years:** without PV $61,000

TESTIMONIAL

We certify every home so it is important everyone on the construction team understands their part in building a high-performance home. This is crucial for maintaining quality construction. The biggest reward is the satisfaction of selling an amazing home and the excitement of our buyers when they let us know how much they enjoy their homes, how comfortable they are, and how low their energy bills are.
- Damian Mora, energy-efficiency coordinator, Garbett Home

KEY FEATURES

- Energy / Heat recovery ventilator
- Raised-heel trusses
- ACH 50 < 2.5 or CFM50/SF of enclosure ? 0.25
- Hot Water Recirculation Pump

CONTACT

(801) 456-2430