

S. D. Jessup Construction

DeepWell Property | Pilot Mountain, NC | SDJessup.com















PROJECT DATA

- Layout: 3 bdrm, 3.5 bath, 2 fls+bsmt, 5.396 ft²
- Climate: IECC 4A, mixed-humid
- Completed: May 2020
- Category: Custom for Buyer >3000 ft²

MODELED PERFORMANCE DATA

- HERS Index: without PV 43; with PV 24
- Annual Energy Costs: without PV \$2,200; with PV \$1,450
- Annual Energy Cost Savings: (vs typical new homes) without PV \$2,500; with PV \$3,300
- Annual Energy Savings: without PV 19,400 kWh; with PV 26,000 kWh
- Savings in the First 30 Years: without PV \$101,800; with PV \$134,000

CONTACT

Shawn D. Jessup 336-368-1155 shawn@sdjessup.com

KEY FEATURES

- Walls: 2x6, 16" o.c. R-25.6: advanced framed, R-19 fiberglass batts, coated OSB R-6.6 sheathing taped, fiber cement siding.
- Roof: Truss gable roof & rafter shed roof: 5/8" coated OSB sheathing taped, self-adhered membrane at valleys, eaves, and low slopes; asphalt shingles and metal cladding.
- Attic: Vented 2nd floor attic: 19" R-50 blown-in fiberglass; 1st floor attic: 9" R-38 open-cell spray foam on underside of roof sheathing, 24" raised heel energy trusses.
- Foundation: Insulated basement: pre-cast concrete walls with integrated foam-insulated concrete studs with metal nailer facings; + R-10 rigid on sill plate. Spray foam at rim band.
- Windows: Triple-pane, argon-filled, low-e2, fiberglass frame, fixed & casement styles, interior shades, U=0.17 (fixed), 0.20 (casement), SHGC=0.25.
- Air Sealing: 1.09 ACH50. Foundation wall joints caulked, wall seams and holes taped.
- Ventilation: ERV with MERV 8 and 13 filters, supplies to return side of HVAC.
- HVAC: Central air-source heat pump, 9.5 HSPF, 18.5 SEER. Three floors/zones with 3 smart thermostats with humidity sensors to control an additional dehumidifier.
- Hot Water: Heat pump water heater, 50-gal, 3.5 EF. 2nd electric tankless water heater.
- Lighting: 100% LED, motion sensors on exterior lights, large windows.
- Appliances: ENERGY STAR refrigerator, dishwasher, exhaust fans.
- **Solar:** 5.27 kW.
- Water Conservation: Low-flow fixtures, compact PEX plumbing.
- Energy Management System: Wi-Fi thermostats, water heater, PV, and monitor.
- Other: Accessible floorplan, hallways, doors, showers. Low/no-VOC paint, caulk, glue, stain.





